

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T 47N R 9W	I11
	T _____ R _____	_____
2. Property Controlling in Section	S 34 T 47N R 9W	2
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11									●				
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 04/03/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(2-Sec. 34) East 1/16 corner between Sections 27 and 34. 1965 - Established by Frank J. Bray RLS midway and on line between Section corner to east and Quarter corner to west. Set 1" iron pipe with 4" aluminum cap. 6" J.Pine S85E 10 links, 4" J.Pine S56W 08 links.

(I11) Corner common to Sections 26-27-34-35. 1963 - Reestablished by Billy D. Buckler RLS by double proportionate measurement between corners 1.5 miles east, 3 miles west, 1 mile south, and 1/2 mile north. Set 1" Iron pipe with 4" aluminum cap. 10" J.Pine N71E 11.5 links, 8" J.Pine N12W 19 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2-Sec. 34) Found the 1965 monument in good condition and at record bearing and distance from the 1965 witnesses, now both dead. The monument was found to be substantially at the midway position noted in the record and I accepted same as a careful and faithful establishment of the position of the corner.

(I11) Recovered the 1963 monument in good condition and at record bearing and distance from the 1963 witness trees, now both dead. Left the monument in place and made new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 4" Tamarack N63E 23.0' mrkd "E1/16 BT"
 4" J.Pine S65E 24.7' do
 4" J.Pine S50W 59.0' do
 5" Tamarack N24W 63.75' do
 Bearings are magnetic.

(I11) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 4" J.Pine N75E 18.8' mrkd "S26 NBT"
 5" J.Pine S47E 44.45' "S35 NBT"
 6" J.Pine S07E 34.6' "S35 NBT"
 7" Tamarack S48W 17.5' "S34 NBT"
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 04/09/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

