

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 47N R 9W	I12
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S 34 T 47N R 9W	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34	●	35		36	
13								●					

I, Stephan J. Szyszkoski, in a field survey on 03/17/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I12) Quarter corner common to Sections 34 and 35. 1963 - Reestablished by single proportionate measurement, midway and on the Section line between Section corners, by Billy D. Buckler RLS. Set 1" Iron pipe with 4" aluminum cap. 7" J.Pine S30W 63.5 links, 9" J.Pine N22E 28.5 links.

(11-Sec. 34) Southwest 1/16 corner, Section 34. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I12) Found the 1963 monument in good condition and at record bearing and distance from the 1963 witnesses. The J.Pine SW is in good condition. The J.Pine NE is standing dead. The monument was found to be substantially at the record proportionate position. I accept same as a careful and faithful reestablishment of the position of the original corner.

(11-Sec. 34) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I12) Found 1" ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 5" Tamarack N63W 10.05' mrkd "1/4S NBT"
 12" J.Pine S32W 42.25' open blazes (1963 NBT)
 12" J.Pine N41E 34.2' mrkd "1/4S NBT"
 9" J.Pine S41E 38.75' do
 Bearings are magnetic.

(11) Set 1" IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Spruce S47W 2.76' mrkd "SW1/16 BT"
 6" Maple N32W 8.4' do
 6" Maple in clump S26E 15.34' do
 12" Tamarack S03W 28.65' do
 Bearings are magnetic.

Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 04/09/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

