

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 34 T 47N R 9W	12
	S 34 T 47N R 9W	16
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on 03/17/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(12-Sec. 34) South 1/16 corner, Section 34. Not established in the original survey. 1965 - T.J.McLaren set post and iron for Cleveland-Cliffs Iron Company "at intersection of corrected N & S 1/4 line and corrected S 1/16 lines". Tam 12 N12W 7.4', Tam 10 N80E 12'.

(16-Sec. 34) East 1/16 corner between Section 34 T47N-R09W and Section 3 T46N-R09W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12-Sec. 34) Recovered a 1" square iron rod, presumably the 1965 monument. I did not accept it as marking the position for the corner. The monument is not located at the record position, and the 1965 method used to determine the corner position is not proper. The monument does not appear to have been relied upon as the corner by local land owners. There is no evidence of improvements in the are and the 1965 position was not marked by any accessories indicating its acceptance as a title corner by any party. I established the corner midway and on a straight line between Center of Section 1318.38' north and Quarter corner 1318.38' south. The 1965 monument was found 4.4' south and 28.2' west of the position thus established.

(16-Sec. 34) Established the corner midway and on the Township line between Section corner 1321.79' east and Quarter corner 1321.79' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 7" Maple S69E 30.65' mrkd "S1/16 BT" 13" Tamarack S12W 23.27' do 6" Maple N76W 32.9' do 1" sq. iron rod S86W 28.59' Bearings are magnetic.	(16) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 10" Tamarack S53E 19.47' mrkd "E1/16 BT" 13" Tamarack N30E 22.27' do 6" W.Birch N14E 34.8' do 8" W.Birch S72W 33.1' do Bearings are magnetic.
---	--

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 04/09/2008

For the Michigan Department of Natural Resources, Office of Land and Facilities

