

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 34 T 47N R 9W	9
	S 34 T 47N R 9W	15
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on 03/17/2008 do hereby state
 that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
 above were in conformance with regulations and rules therefore as required in the current manual of survey
 instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
 a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
 the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
 re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded
 on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(9-Sec. 34) East 1/16 corner, Section 34. Not established in the original survey. 1965 -
 T.J.McLaren, for Cleveland-Cliffs Iron Company set post and iron "on corrected E-W 1/4 line 20.00
 chains W. of established 1/4 cor.". J.Pine 5 N40E 7.4'.

(15-Sec. 34) West 1/16 corner between Sec. 34 T47N-R09W and Sec. 3 T46N-R09W. Not established in the
 original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(9-Sec. 34) Recovered a 1" square iron rod, presumably the 1965 monument. I did not accept the
 monument as marking the position for the corner. The monument is not located at the position
 described in the 1965 record and the method used to determine the corner position is not proper. The
 monument does not appear to have been relied upon as the corner by local land owners. There is no
 evidence of improvements in the area and the 1965 position was not marked by any accessories
 indicating its acceptance as a title corner by any party. I established the corner midway and on a
 straight line between Center of Section 1319.47' West and 1/4 corner 1319.47' East. The 1965
 monument was found 25.1' West and 3.8' North of the position thus established.

(15-Sec. 34) Established the corner midway and on the Township line between Section corner 1321.19'
 west and Quarter corner 1321.19' east.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(9) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 5" J.Pine N37W 31.0' mrkd "E1/16 BT"
 9" Tamarack S43W 25.68' do
 9" Tamarack S54E 35.7' do
 1" sq. iron rod N78W 25.4'
 Bearings are magnetic.

(15) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.
 The corner falls in a tag alder marsh. No witness
 trees were available for accessories.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 04/09/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities