

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 27 T 47N R 9W _____	13
	S 27 T 47N R 9W _____	14
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 13 04/14/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 27) Southeast 1/16 corner, Section 27. Not established in the original survey.

(14-Sec. 27) South 1/16 corner between Sections 26 and 27. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 27) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

(14-Sec. 27) Established the corner midway and on the Section line between Quarter corner 1319.18' north and Section corner 1319.18' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 6" Tamarack S35W 23.25' mrkd "SE1/16 BT"
 5" Tamarack N70E 18.0' do
 6" Tamarack N40E 17.4' do
 5" B.Spruce N88W 7.9' do
 Bearings are magnetic.

(14) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 5" Tamarack N54E 13.25' mrkd "S1/16 BT"
 5" Tamarack S87W 5.78' do
 7" Tamarack N05E 14.18' do
 5" Tamarack S34E 12.37' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 09/08/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities