

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR. 10. W

Lucas COUNTY

DESCRIPTION OF CORNER ~~1/4 corner between Sections 31 and 32~~

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 10" W. Pipe (NG) N 74° E 99 1/2 Links

Corner lies 18 1/2 links east of telephone line and

33 links south of south edge of E.-W. Road

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established in line with fence line to west which appears to have been built on the E - W. Quarter line and in line with Section corners North and south. This position checks very close to proportionate measure north and south.

Corner was placed and witnessed May 12, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

Billy D. Beckler
REGISTERED LAND SURVEYOR
Billy D. Beckler

DATE 5/23/60