

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 47 N. 2. R. 10 E.	B-3 C-2
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 12/1 1969, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

B-3     , Cor. bet. Secs: 6-7, was place by Geo. H. Cannon, D.S. 1853, while making a correctional survey of this township. Bearings were: Beech 10" S38°W 30 Links, and Hemlock 12" N41°E 32 Links.

C-2     , Cor. bet. Secs: 5-6, placed by Geo. H. Cannon, D.S. 1853. Bearings were: Hemlock 12" N30°E 4 lks. and Hemlock 10" S30°E 15 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

B-3     Corner re-established by single proportionate measure bet. two Sec. Cors. Found no evidence of original corner. Corner is located on NW corner of a wet marsh.

C-2     Corner re-established on line and by single proportionate measure bet. two Sec. Cors. Found no evidence of original corner. Corner lies on west edge of swamp.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed 1" pipe with 4" aluminium cap at both corners.

B-3     New Bearings:     . Birch N07°E 36.3'  
                               W. Birch S17°E 34.7'

C-2     New Bearings:     6" Cedar N72°W 32.0'  
                               7" W. Birch S05°E 19.9'

*Billy D. Buckler*

SIGNED BY Billy D. Buckler DATE 1/4/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8827 (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO.