

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Four Corners

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|--------------------------------------|---------------------|--------------------|
| 1. PUBLIC LAND SURVEY | T. 47 N., R. 16 E. | C-5, C-4, B-5, B-7 |
| 2. PROPERTY CONTROLLING IN SECTION | T. N. S., R. E. W. | |
| 3. MISCELLANEOUS PROPERTY IN SECTION | T. N. S., R. E. W. | |
| 4. LOT NO. _____ | RECORDED PLAT _____ | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Luckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on 1-2 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
interior corners of this township, set by Geo. H. Cannon, D.S. in 1853, while making a Correctional Survey of this township.

Bearings were:

| | | | | | |
|-----|-----------|-------|--------------------------|-------|---------|
| C-5 | Beech 7" | S12°E | 25 lks. and Y. Birch 10" | S22°W | 30 lks. |
| C-4 | Beech 9" | S82°E | 13 lks. and Beech 9" | S67°W | 17 lks. |
| B-5 | Beech 8" | S5°E | 33 lks. and Sugar 8" | S38°E | 45 lks. |
| B-7 | Maple 12" | N70°W | 19 lks. and Hemlock 10" | S73°E | 25 lks. |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 C-5 Re-established; Cor. bet. Secs. 7-17-18, by single proportionate measure, bet. corners, one mile North and 1/2 mile South.
 C-4 Re-established; Cor. bet. Secs. 7-8, by single proportionate measure, bet. Sec. Cors. 1/2 mile to North and South.
 B-5 Re-established; Cor. bet. Secs. 7-18, by single proportionate measure, bet. Sec. Cors. 1/2 mile to East and West.
 B-7 Re-established; Cor. bet. Secs. 18-19, by single proportionate measure, bet. Sec. Cors., 1/2 mile to East and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap at all corners.

New Bearings:

| | | | | | |
|-----|----------------|-------|-------------------------|-------|-------|
| C-5 | 10" Soft Maple | S69°W | 9.5' and 8" Soft Maple | S43°W | 9.3' |
| C-4 | 30" W. Pine | S42°E | 23.5' and 8" Soft Maple | S51°W | 23.8' |
| B-5 | 10" W. Pine | S23°E | 26.2' and 6" W. Spruce | S44°E | 17.6' |
| B-7 | 10" Cherry | S25°E | 11.9' and 12" Cherry | S66°W | 39.5' |

SIGNED BY Billy D. Luckler DATE 8/8/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8882 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____