

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Lucas Co.

Three Corners.

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 10 W.	E-11, E-9, F-11
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 6-21 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_ found, recovered, restored established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

This Twp. originally set by Geo. H. Sutton D.S. in 1853, while making a correctional Survey of this Twp.

- E-11 Sec. Cor. 21-22-23. Bearings were: Beech 12", S57°W, 30 lks.  
Beech 12", N45°E, 66 lks.
- E-9 Sec. Cor. 20-21-22. Bearings were: Sugar 14", N76°W, 32 lks.  
Beech 12", S38°E, 28 lks.
- F-11 Sec. Cor. 20-21. Bearings were: Sugar 8", N3°E, 25 lks.  
Beech 14", S7°W, 38 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- E-11 Set at Sq. east set by old town Surveyors, 4.0' west. Corner lies 24' North of 211' long line. Set by 1/4 mile proportionate measure and record bearing bet. corners one mile to East and one mile to West.
- E-9 Corner re-established by 1/4 mile proportionate measure bet. corners, one mile North and one mile South.
- F-11 Corner set by 1/4 mile proportionate measurement bet. Sec. Cor. to East and Sec. Cor. to West. Cor. lies 3.0' NE of old R.R. grade - NW-SE.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

All Three Corners 1" x 36" pipe with dept. cap.

- E-11 New Bearings: 8" H. Maple N75°W 20.7' and 8" H. Maple N2°E 19.0'
- E-9 New Bearings: 7" H. Maple N4°W 9.4' and 6" H. Maple S21°E 37.0'
- F-11 New Bearings: 10" Maple S64°W 66.9' and 5" Apple N59°W 26.0'

SIGNED BY: Billy D. Buckler

DATE: 6-13-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8857

(SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_