

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
 Luce Co. Three Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 47 N. R. 10 W.	D-7 16, Sec. 17 15, Sec. 17
2. PROPERTY CONTROLLING IN SECTION 17	T. 47 N. R. 10 W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on 5/7 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_ found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and, or subsequent restoration:  
 This Prop. originally set by Geo. B. Jackson D.S. in 1853, while making a correctional Survey of Pwa.  
 D-7 Cor. bet. Secs. 17-20. Bearings were: Beech 8", N11°E, 201'  
Beech 8", S3°W, 361'  
 16, Sec. 17 East 1/16 Cor. bet. Secs. 17-20.  
 15, Sec. 17 East 1/16 Cor. bet. Secs. 17-20.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 D-7 Corner re-established, using and in line bet. two Secs. Cors.  
 Found evidence of original corner.  
 16, Sec. 17 Corner placed equal-distant, on the East 1/2 mile.  
 15, Sec. 17 Corner placed equal-distant, on the West 1/2 mile.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 D-7 1" x 36" pipe with brass Dept. Cap placed at corner.  
 New Bearings: 9" Hard Maple, S19°E, 9.0' and 9" Hard Maple, N79°E, 14.9'  
 16, Sec. 17 1" x 36" pipe with brass Dept. Cap placed at corner.  
 New Bearings: 8" Hard Maple, West, 18.3' and Corner lies 36.0' South of EC  
 15, Sec. 17 1" x 36" pipe with copper Dept. Cap placed at corner.  
 New Bearings: 8" Maple, N47°E, 8.1' and 8" Maple, N67°E, 13.4'

SIGNED BY Billy D. Buckler DATE 2/13/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)