

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Lucas Co.

Three Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	E. 47 th N. R. 10 th W.	E-5, C-0, 14, Sec. 8
2. PROPERTY CONTROLLING IN SECTION	E. 47 th N. R. 10 th W.	
3. MISCELLANEOUS PROPERTY IN SECTION		
4. LOT NO. RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 5/23/73 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior - Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 10/11/73 found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and, or subsequent restoration:
 This is the corner of the 1/4 Sec. 8, T. 47 N., R. 10 W., Sec. 8, T. 47 N., R. 10 W., 14, Sec. 8 Canon D.S. in 1853, while making a corner survey of this Co.
 E-5 corner. Dir. 185-21-17. Bearings were: 1" Birch 9", S85°E, 161ks.
 Spruce 14", N74°E, 371ks.
 C-8 corner. Dir. Sec. 1420. Bearings were: Beech 14", S52°E, 161ks.
 Beech 7", S41°W, 61ks.
 14, Sec. 8, T. 47 N., R. 10 W., 14, Sec. 8

B. Description of corner evidence found and or method applied in restoring or re-establishing corner:
 E-5 corner. Restored by setting monument in 1870 by surveyor.
 C-8 corner. Restored by setting monument in 1870 by surveyor.
 14, Sec. 8 corner. Discovered on line bet. Sec. Cor. to the South and 1/4 Cor. to the North.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 E-5 1" x 36" pipe with dept. cap. New Bearings: 6" Cedar, N35°W, 35.0'
 (Corner lies in Black Spruce swamp on N-S line) 5" Cedar, N70°E, 31.6'
 C-8 1" x 36" pipe with dept. cap. New Bearings: 16" Y. Birch, S33°E, 53.2'
 (Line 150' East of Old Co. Rd. 402) 8" Maple, N43°W, 32.9'
 14, Sec. 8 1" x 36" pipe with dept. cap. New Bearings: 8" Cedar, S71°W, 19.3'
 14" Cedar, North, 21.2'

SIGNED BY: Billy D. Buckler DATE: 8/13/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8867 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY: _____ DATE: _____
 CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY: _____ DATE: _____
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)