

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co. Two Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. S. R. <u>10</u> PK W.	<u>D-11</u> <u>E-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		


REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 8-3 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- D-11 1/4 Cor. bet. Sec's. 29-32, set by Geo. H. Cannon D.S., while making a Corrected Survey of this twp. 1853.
Bearings were: Y. Birch 11", N70°E, 32 lks. and Beech 6", S38°W, 22 lks.
 - E-7 Sec. Cor. 16-17-20-21, set by Geo. H. Cannon D.S. 1853.
Bearings were: Cedar 13", S69°W, 13 lks. and Y. Birch 11", N69°E, 26 lks.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- D-11 Corner placed midway and on line bet. two Sec. Cors. No evidence of original corners.
 - E-7 Corner replaced at a squared Birch tree, several old blazes facing corner. Possible Cedar witness trees, but nothing definite.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- D-11 Placed 1" pipe with 4" aluminium cap at corner.
New bearings: 6" Maple, N12°E, 8.1' and 8" Maple, S81½°E, 30.8'
 - E-7 Placed 1" pipe with 4" Brass cap at corner.
New bearings: 8" Cedar, N75°W, 10.3' and 11" Cedar, S17°W, 34.1'

SIGNED BY Billy D. Buckler DATE 2-22-74

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR