

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47-48 N.R. 10 W

Luce


COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 4-5, T47N R10W & 32-33, T48N R10W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 3/17/64

WITNESSES TO CORNER.....14" W. Pine, S33 NBT), N 57° E, 687 Lks.



CIRCLE CORNER REGISTERED

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by placing on Line and the Single Proportioned measurement between Town Corner to East and 1/4 Corner 1/2 mile to West.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 4/29/1966
REGISTERED LAND SURVEYOR