

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 & 48 N. R. 10 W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 3-4 T47N R10W & 33-34 T48N R10W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 3/17/64

WITNESSES TO CORNER..... 14" W. Pine (S33 MBT) N57°E 687 Lcs.



CIRCLE CORNER REGISTERED

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by placing on Line and the Single Proportioned measurement between Town Corner To East and 1/4 Corner 1/2 mile to West.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/17/1964
REGISTERED LAND SURVEYOR