

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 9-10W


Luce COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Secs. 19-24

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/2/63

WITNESSES TO CORNER..... 16" Red Pine ($\frac{1}{4}$ S NBT) S74°W 45 $\frac{1}{2}$ Lks.



15" Red Pine ($\frac{1}{4}$ S NBT) N65°E 30 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by Single Proportionate Measure along Township line. Found two old witnesses marked by unknown Surveyor. A 24" Red Pine N75°E 29 Links and an 18" W. Pine S82°W 36 $\frac{1}{2}$ Links. Blazes appear to face the re-established corner.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED BILLY D. BUCKLER DATE 7/31/1964
REGISTERED LAND SURVEYOR