

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N. R. 10W


Ince COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 1 27-28-33-34

CORNER MONUMENT 1" Iron pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 1/24/64 with Forestry Aide Rubick

WITNESSES TO CORNER..... 8" Cedar (S34 NBT) S48°E 36 $\frac{1}{2}$ Lks.



6" Cedar (S33 NBT) S42°W 28 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from Cedar Stump on which overgrowth showed inverted mark of Scribing (Cedar 8" N45°W 19 Links.) There's mound proper distance and bearing for Cedar 16" N03°E 17 Links.

SURVEYOR'S SEAL

Frank J. Bray
SIGNED Frank J. Bray DATE 8/11/1964
REGISTERED LAND SURVEYOR