

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 47. NR 10 W.

Luce

COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 5-6-7-8  
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap  
WITNESSES TO CORNER 7" W. Pine N 82° E 39 links  
"S 5 NBT"  
6" Balsam S 22° E 28½ links  
"S 8 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced corner as set by H. Lawrence, registered surveyor. Found yellow birch B.T. bearing S 15° W 13 links in fair condition. Also found hemlock B.T. (noted as old witness in field notes) bearing S 30° E 11 links in fair condition.

Found by District Forester. Corner lies on west edge of high ground island. Placed location poster on road 17.00 chs. west of corner.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 11/13/57  
REGISTERED LAND SURVEYOR