

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 NR 10 W

Luce

COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sec.'s 29-30

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 12" Jack pine S 67° E 100 1/2 links
"1/4 S NBT"

16" W. Pine S 56° W 112 links
"1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 corner from original tamarack line tree 8.65 chs. south.

Found no evidence of 1/4 corner. Extended line north from section corner 29-30-31-32 thru line tree and placed 1/4 corner at record distance.

Corner lies in old road bed.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 11/13/57
REGISTERED LAND SURVEYOR