

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 47 N.R. 10-11 W


Luce COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 18, 19, 13, 24

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9/9/60 with L. Rubick, Aide.

WITNESSES TO CORNER.....8" W. Pine (S 13 NBT) N 88° W 49 1/2 Links



7" W. Pine (S 24 NBT) S 53° W 44 1/2 Links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced at old fence Iron and wood post, Set by unknown surveyor. Found 24" W. Pine Stump bearing N 77° E, 27 Links, for one probable B.T. Blazes and axe marks on stump. Placed location poster 14 chains north on road. Corner found by L. Rubick, Aide.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 5/25/61  
REGISTERED LAND SURVEYOR  
Billy D. Buckler