

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 10-11 W


Luce COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 6, 7, 1, 12

CORNER MONUMENT 1" Pipe with 4" Brass Cap

DATE MONUMENT PLACED AND WITNESSED 9/9/60 with L. Rubick, Aide.

WITNESSES TO CORNER.....11" Aspen (S 7 NBT) S 61° E 17 Links



6" Soft Maple (S 1 NBT) N 54° W 102½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced at old scribed post set by unknown surveyor. No evidence of original corner. Round marsh 1 chain east as per government notes. Corner found by L. Rubick, Aide. Corner lies 1 1/4 chains south of road.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 5/25/61
REGISTERED LAND SURVEYOR
Billy D. Buckler