

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 N.R. 9 & 10 W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 12, 13 T47N R10W & 7, 18 T47N R9W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 3/25/64 with Forestry Aide Rubick, Hinds, Alatalo

WITNESSES TO CORNER..... 10" J. Pine (S13 MBT) S22°W 87 lks.



26" W. Pine (S18 MBT) S31°E 86 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by placing on line and the Single Proportioned measurement between 1/4 Corner 1/2 mile South and Town Corner 2 miles North.

SURVEYOR'S SEAL

SIGNED Frank Bray DATE 8/11/1964
REGISTERED LAND SURVEYOR