

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 47 N.R. 9210W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 1, 12 T47N R10W & 6, 7 T47N R9W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 3/25/64 with Forestry Aide Kubick, Hinds & Alatalo

WITNESSES TO CORNER..... 8" J. Pine (S 7 NBT) S42°E 79 Lks.



4" Tamarack (S1 NBT) N27°W 26 1/2 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by placing on Line and Single Proportioned measurement between Town Corner 1 mile to North and 1/4 Corner 1 1/2 miles to South.

SURVEYOR'S SEAL

SIGNED Frank Bray DATE 8/11/1964  
REGISTERED LAND SURVEYOR