

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

4 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 47 N. E. R. 10 W.	J-12 15-Sec.35, 8-Sec.35 9-Sec.35
2. PROPERTY CONTROLLING IN SECTION	35, T. 47 N. E. R. 10 W.	
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-30, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- J-12 Center Corner of Section 35.
- 15-Sec.35 West 1/16 Corner, on South side of Section 35.
- 8-Sec.35 West 1/16 Corner of Section 35.
- 9-Sec.35 East 1/16 Corner of Section 35.


**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- J-12 Placed corner at intersection of lines connecting opposite quarter corners.
- 15-Sec.35 Placed corner midway bet. Sec. Cor. to West and a fence line, road intersection at the Quarter corner, to East. Found an old fence North and South of road 4.0' West of corner.
- 8-Sec.35 Established corner midway bet. Center corner and West 1/4 corner.
- 9-Sec.35 Established corner midway bet. Center corner and the East 1/4 corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- J-12 Placed 1" pipe with 4" alum. cap at corner. Bearings: 5" R. Maple, N85°E, 7.5'. & 6" W. Birch, N79°W, 20.2' & 10" W. Birch, S38°W, 46.5'.
- 15-Sec.35 Drove a 36" T-Iron in North edge of Blacktop. Bearings: 6" R. Maple, N12°E, 56.6' & 16" W. Birch, N19°W, 77.5'.
- 8-Sec.35 Placed 1" pipe with 4" alum. cap at corner. Bearings: 10" W. Birch, S44°W, 25.0' & 10" W. Birch, N19°W, 20.3' & 10" W. Birch, N65°E, 18.3'. Corner lies 40' West of N-S woods road.
- 9-Sec.35 Placed 1" pipe with 4" alum. cap at corner. Bearings: 6" R. Maple, S7°W, 5.0' & 5" R. Maple, S79°E, 14.3' & 5" R. Maple, N5°W, 10.7'.

SIGNED BY Billy D. Buckler DATE 5-4-81  
 Billy D. Buckler  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_