

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

1 Corner.

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. <u>8</u> , R. <u>10</u> E.	<u>C-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-6, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C-9 S.E. Section Corner of Section 19. D.N.R. L.S. Billy D. Buckler placed a 3/4" x 32" pipe on 6-4-75. Bearings: 8" Maple, N61°E, 77.8' & 10" Maple Clump, S62°W, 47.2'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-9 Buckler placed this corner by proportionate measure from corners to East and West and in line with old fences. Corner lies in East edge of old road bed. Re-Witt. this corner as the bearings were recorded wrong.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 1" pipe W/plastic RLS Cap. Bearings: 10" Maple Clump, N61°W, 47.2'  
 8" Maple, S67°W, 77.8'  
 8" Maple, N84°E, 43.0'  
 10" Beech, N82°W, 73.2'

SIGNED BY

Gerald L. Wiggins  
 Gerald L. Wiggins

DATE 9-19-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

