

#69

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Locality	Located In:	Corner Code //
1. Public Land Survey	T 47N R 10W	N13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 18 T 47N R 10W	5
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

N13 July 13, 1992

I, Stephan J. Szyszkoski, in a field survey on October 01, 1992, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(N13) Quarter corner common to Section 34, T47N-R10W and Section 3, T46N-R10W. Corner previously recorded by Billy D. Buckler as recovered and monumented in 1956, according to original evidence. Buckler's now bearing trees are: 10" Cedar N82E 10 Links, marked "1/48 NBT"; 11" Cedar S23W 15.5 Links, marked "1/48 NBT".

(5) North 1/16 corner, Section 18. Corner not established in original survey. Found no other record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(N13) Found no evidence of Buckler's monument, recorded as a 1" pipe with a 4" brass cap. Monumented the corner in accord with Buckler's bearing trees, both recovered as recorded. At the position for the corner, I placed a 1"x32" painted iron pipe capped with a cast aluminum Michigan Dept. of Natural Resources tablet, appropriately stamped. Remarked the top blaze on Buckler's Cedar N82E, and top and bottom blazes on his Cedar S23W. Marked two new bearing trees, as described below.

(5) Established corner equidistant and on a straight line between the North 1/4 corner of Section 18, recorded by Billy D. Buckler in 1973, and the Center of Section 18, recorded by Billy D. Buckler in 1981. Found the distance between these two previously recorded corners to be 2637.18 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(N13) Set a 1"x32" pipe with HDNR cap. Blazed, scribed, and set measuring nails in the following new bearing trees:  
6" Cedar S53E, 10.05', mrd "1/48 NBT"  
10" Cedar S28E 8.0', mrd "1/48 NBT"  
Placed measuring nails in Buckler's BT's as follows:  
12" Cedar N82E 7.22'  
13" Cedar S23W 10.35'



(5) Placed a 1"x32" painted iron pipe capped with a cast aluminum HDNR tablet. Blazed, scribed, and set measuring nails in the following bearing trees:  
8" Maple N33W, 20.2'(slope), "1/16 BT"  
8" Maple N37E, 36.8', "1/16 BT"  
10" W. Pine S87E, 50.32', "1/16 BT"  
9" W. Pine S53E, 61.3', "1/16 BT"

Signed by Stephan J. Szyszkoski Date 10-15-1992  
Surveyor's Michigan License No. 33986