

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Luce

	(County)	Located In:	Corner Code =#
1. Public Land Survey		T <u>47N</u> R <u>10W</u>	<u>C3</u>
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S <u>6</u> T <u>47N</u> R <u>10W</u>	<u>7</u>	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

C3 June 19, 1995

I, Stephan J. Szyszkoski, in a field survey on 7 May 08, 1995, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(C3) Corner common to Sections 5-6-7-8. Corner re-monumented in 1957 by Billy D. Buckler, RLS, from original bearing trees, both in fair condition. Buckler placed a 1" iron pipe with 4" brass cap and the following witnesses: 7" W. Pine N82E 39 links, 6" Balsam S22E 28.5 links. Found no subsequent record.  
 (7-Sec. 6) North 1/16 corner between Sections 5-6. Corner not established in the original survey. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(C3) Found and accepted Buckler's monument, in good condition, and at record bearing and distance from the 1957 W. Pine witness. The 6" Balsam was not recovered. Left the monument in place, remarked the top blaze of the W. Pine, and marked three new accessories as described below.  
 (7-Sec. 6) Found no evidence of prior monumentation at the corner position. Established the corner on a straight line between 1/4 corner 1314.67' south and Section Corner 1523.71' north, the position being 20 chains, proportionate measure, north of the 1/4 corner. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(C3) Found 1" pipe with 4" brass MI Dept. of Conservation cap. Blazed and scribed the following:	(7) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following bearing trees:
14" W. Pine N82E 26.2' "S5 NBT"	4" Balsam S25W 11.3' "N1/16 BT"
8" Maple N62E 21.4' "S5 NBT"	6" W. Birch S22E 3.95' "N1/16 BT"
4" W. Birch S53E 11.8' "S8 NBT"	6" W. Birch N51E 18.65' "N1/16 BT"
4" Spruce S35W 13.6' "S7 NBT"	4" W. Birch N29E 2.6' "N1/16 BT"
Found two old squared and scribed cedar posts adjacent. Bearings are magnetic.	Placed a 4" squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 6/28/95  
 Surveyor's Michigan License No. 33986