

76

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

(County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>6</u> T <u>47N</u> R <u>10W</u>	<u>12</u>
	S <u>6</u> T <u>47N</u> R <u>10W</u>	<u>14</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on June 19, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(12-Sec. 6) South 1/16 corner, Section 6. Corner not established in the original survey. Found no subsequent record.
 (14-Sec. 6) South 1/16 corner between Sections 5-6. Corner not established in the original Survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12-Sec. 6) Found no evidence of prior monumentation at the corner position. Established the corner on a straight line between Center of Section 1318.79' North and 1/4 Corner 1318.79' South. At the position for the corner, I placed a 1"1.0.x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I found a 2" iron pipe, placed by unknown persons, 62.8' West of the N-S 1/4 line and 0.4' North of the E-W 1/16 line.
 (14-Sec. 6) Found no evidence of prior monumentation at the corner position. Established the corner on a straight line between 1/4 corner 1314.67' North and Section corner 1314.67' South. At the position for the corner, I placed a 1"1.0.x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and placed measuring nails in the following bearing trees: 6" Maple N26W 8.6' "S1/16 BT" 4" Maple S50E 9.3' "S1/16 BT" 5" Maple S15E 4.75' "S1/16 BT" 4" Maple S44W 3.45' "S1/16 BT" Placed a 4" squared and scribed cedar post adjacent. Bearings are magnetic.	(14) Set 1" iron pipe with MDNR cap. Blazed, scribed, and set measuring nails in the following bearing trees: 5" Cedar S14E 17.5' "S1/16 BT" 6" Maple S72W 18.4' "S1/16 BT" 6" Cedar N10W 19.8' "S1/16 BT" 5" Spruce N15E 12.9' "S1/16 BT" Placed a 3" squared and scribed cedar post adjacent. Bearings are magnetic.
--	--



Signed by Stephan J. Szyszkoski Date 8/28/95
 Surveyor's Michigan License No. 33986