

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>10W</u>	<u>C1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>6</u> T <u>47N</u> R <u>10W</u>	<u>11</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

11 June 19, 1995

I, Stephan J. Szyszkoski, in a field survey on C1 June 07, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C1) Corner common to Sections 5-6 T47N-R10W and Sections 31-32 T48N-R10W. Corner reestablished in 1964 by Frank J. Bray, RLS as follows: "This corner was re-established by placing on line and single proportioned distance between 1/4 corner 1/2 mile to East and Town Corner 1 mile to West. Placed 1" iron pipe with 4" aluminum cap. Witnesses are 8" J. Pine S38E 165 links, 6" J. Pine N88E 140 links. Found no subsequent record.

(11-Sec. 6) Southwest 1/16 corner. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C1) Found and accepted Bray's monument, as described, in good condition, at record bearing and distance from his 1964 witnesses, now both dead. Left the monument in place and marked four new bearing trees as described below.

(11-Sec. 6) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I recovered a 2" iron pipe, placed by unknown persons, 71.3' west of the N-S 1/16 line, and 0.3' south of the E-W 1/16 line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C1) Found 1" pipe with 4" cap. Blazed, scribed, and set measuring nails in the following bearing trees:

4" Spruce S75E 47.1' "S5 NBT"
 3" Spruce N57E 39.6' "S32 NBT"
 5" Spruce South 57.2' "S6 NBT"
 3" Spruce N55W 9.5' "S31 NBT"

Found a 5" squared and scribed cedar post and a 1/2" iron pipe adjacent to the monument. Bearings are magnetic.

(11) Set a 1" iron pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:

10" R. Pine S79W 16.7' "S1/16 BT"
 12" R. Pine S65W 11.8' "S1/16 BT"
 10" W. Pine S04W 12.8' "S1/16 BT"
 6" W. Pine N83E 4.7' "S1/16 BT"

Placed a 4" squared and scribed cedar post adjacent. Bearings are magnetic.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													



Signed by Stephan J. Szyszkoski Date 8/28/95
 Surveyor's Michigan License No. 33986