

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Luce

| (County)                              | Located In:     | Corner Code # |
|---------------------------------------|-----------------|---------------|
| 1. Public Land Survey                 | T 47N R 10W     | 81            |
|                                       | T R             |               |
|                                       | T R             |               |
|                                       | T R             |               |
| 2. Property Controlling<br>in Section | S 6 T 47N R 10W | 2             |
|                                       | S T R           |               |
| 3. Miscellaneous<br>Property in Sec.  | S T R           |               |
|                                       | S T R           |               |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, in a field survey on June 07, 1995, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

|    |    |    |    |    |    |    |    |    |    |    |    |    |
|----|----|----|----|----|----|----|----|----|----|----|----|----|
| A  | B  | C  | D  | E  | F  | G  | H  | I  | J  | K  | L  | M  |
| 2  | 1  | 2  | 3  | 4  | 5  | 6  | 7  | 8  | 9  | 10 | 11 | 12 |
| 3  |    |    |    |    |    |    |    |    |    |    |    |    |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |    |    |    |    |    |    |
| 5  |    |    |    |    |    |    |    |    |    |    |    |    |
| 6  | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 |    |    |    |
| 7  |    |    |    |    |    |    |    |    |    |    |    |    |
| 8  | 16 | 20 | 21 | 22 | 23 | 24 |    |    |    |    |    |    |
| 9  |    |    |    |    |    |    |    |    |    |    |    |    |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |    |    |    |    |    |    |
| 11 |    |    |    |    |    |    |    |    |    |    |    |    |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |    |    |    |    |    |    |
| 13 |    |    |    |    |    |    |    |    |    |    |    |    |

A. Description of original monument and accessories and/or subsequent restoration:

(81) Quarter corner common to Section 6 T47N-R10W and Section 31 T48N-R10W. Corner reestablished in 1964 by Frank J. Bray, RLS, by single proportionate measurement between adjacent Section corners. Bray placed a 1" iron pipe with a 4" aluminum cap and the following witnesses: 10" Y. Pine S37E 19 links, 6" W. Pine N43E 35.5 links. Found no subsequent record.

(2-Sec. 6) East 1/16 corner between Section 6 T47N-R10W and Section 31 T48N-R10W. Corner not established in the original survey. Corner established by Frank J. Bray, RLS, in 1964, midway between Section corner to east and 1/4 corner to west. Bray placed a 1" iron pipe with 4" aluminum cap and the following witnesses: 9" W. Pine S85E 27 links, 10" W. Pine North 51 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(81) Found and accepted Bray's monument, as described, in good condition, at record bearing and distance from the remaining W. Pine witness. The Y. Pine witness is gone. Remarkd the top blaze on the White Pine and marked three new accessories as described below.

(2-Sec. 6) Found Bray's monument as described, in good condition, at record bearing and distance from his W. Pine accessories, both in good condition. Remarkd the top blaze on the 1964 witnesses and placed measuring nails in them. Marked two new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(81) Found 1" pipe with 4" cap.  
Blazed, scribed, and set measuring nails in the following bearing trees:  
10" W. Pine N43E 23.65' (1964 witness)  
12" W. Pine S80E 23.35' "1/4S NBT"  
6" Spruce N62W 19.25' "1/4S HBT"  
5" Maple S81W 6.6' "1/4S NBT"

Found an old 5" squared and scribed cedar post adjacent. Bearings are magnetic.

(2) found 1" pipe with 4" aluminum cap.  
Blazed, scribed, and set measuring nails in the following:  
12" W. Pine S85E 18.0' (1964 tree)  
14" W. Pine North 33.5' (1964 tree)  
8" Cedar N15W 5.7' "E1/16 BT"  
8" Maple S78W 3.4' "E1/16 BT"  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 8/28/95  
Surveyor's Michigan License No. 33986