

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

(County)	Located In:	Corner Code #
1. Public Land Survey	T 47H R 10W	A3
	T 47H R 10W	A2
2. Property Controlling In Section	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3	7	8	9	10	11	12							
4													
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on May 31, 1995, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A3) Corner common to Sections 6-7 T47N-R10W and Sections 1-12 T47N-R11W. Corner re-monumented in 1961 by Billy D. Buckler, RLS, as follows: "This corner was replaced at old scribed post set by unknown surveyor. No evidence of original corner. Round marsh 1 chain east as per government notes. Corner found by L. Rubick, Aide. Corner lies 1 1/4 chains south of road. Placed 1" pipe with 4" brass cap. 11" Aspen S61E 17 links, 6" Soft Maple N54W 102.5 links." Found no subsequent record.

(A2) Quarter corner common to Section 6 T47N-R10W, and Section 1 T47N-R11W. Corner re-monumented in 1957 by Billy D. Buckler, RLS, as follows: "Replaced 1/4 corner as set by H. Lawrence, reg. surveyor. Found wood post in place. Found no conclusive evidence of original B.T.S. 1/4 corner lies in swamp. Found by B. McTiver, District Forester. Corner placed and witnessed Dec. 20, 1957. Placed 1" pipe with 4" brass cap. Witnesses: 4" Cedar S70W 30 links, 6" B. Spruce N22E 34 links". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A3) Found and accepted Buckler's monument as described, in good condition, and at record bearing and distance from his two accessories. The Aspen is now 20" dia. and the Maple has been cut. Also found W. Pine marked by a local surveyor (scribed S6 NBT).

(A2) Found and accepted Buckler's monument, as described, in good condition, at record bearing and distance from the remaining 1957 cedar witness. Placed measuring nail in the cedar, remarked the top blaze, and marked three new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A3) Found 1" pipe with 4" brass cap. Blazed, scribed, and placed measuring nails in the following:
 20" Aspen S61E 11.3' "S7 NBT"
 10" W. Pine N47E 24.65' (found marked)
 6" Maple N20E 30.6' "S6 NBT"
 3" Maple S28E 16.0' "S7 NBT"
 A 4"x4" squared and painted post is adjacent to the monument. Placed a location poster on a 12" W. Pine 85' north of the corner on south side of

(A2) Found 1" pipe with 4" brass cap. Blazed, scribed, and set measuring nails in the following:
 10" Cedar S70W 20.25' (1957 tree)
 6" Spruce S14W 44.7' "1/4S NBT"
 6" Maple N20E 12.45' "1/4S NBT"
 8" Cedar N33W 25.4' "1/4S NBT"
 Found old squared and scribed cedar post and newer squared post, painted blue, adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 8/28/95
 Surveyor's Michigan License No. 33986