

SURVEY & REMONUMENTATION

MAY 28 1997

LUCE COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Luce</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T46N R10W	D-1 Same
	T47N R10W	D-13 Corner
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

REGISTER OF DEEDS
Recorded
Liber 2 Page 706
02-28-1997 08:53:43
Kathy S. Mahar
Kathy S. Mahar, Register
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 12/10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:


A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

Twp 46 N R 10 W

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1 (D-13) 1/4 Corner Common to Section 5, T46N, R10W & Section 32, T47N, R10W
1841 - Original ties to set post (John Burt): Beech 12, N14°E 31 links - Beech 5, N45°W 26 links.
1960 - Billy D. Buckler, RLS 8887, page 409A of Luce County recorded corners. Corner re-established midway and on line between section corners. Found no evidence of original corner. Corner lies on south edge of road.
Witnesses: 6" Hard Maple, S25°E 73 links - 6" Hard Maple, S30°W 72½ links.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Luce County Remonumentation Program.
Found a 1" iron pipe on the north side of a pointed top wooden post, on the south side of County Road. Also found Buckler's bearing tree to the southeast. Accepted corner as found and established new additional witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is 1" iron pipe on the north side of a pointed top wooden post, 35 feet south of the centerline of County Road 407. Witnesses:
10" Sugar Maple, S25°E 48.20' (existing bearing tree)
Power Pole, N18°W 67.81'
11" Sugar Maple, S03°E 29.57'
12" Sugar Maple, S29°W 45.92'



Note: Distances are to a nail/tag P.S. 33142 in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96