

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

(County)

Located In:

Corner Code #

1. Public Land Survey

T 47N R 10W A12
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling
 in Section

S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous
 Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sep 18 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 Quarter corner common to Section 31 T47N-R10W and Section 36 T47N-R11W. Corner re-monumented in 1960 by Billy D. Buckler RLS: This corner was reestablished 50 links to west of old fence corner. Fence appears to have been built with an allowance for a road along the section line to south and on east-west quarter line. 1" pipe with 4" brass cap. 13" Red Pine N54W 155 links, 7" B.Cherry S79E 76.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 The Luce County Road Commission reported that this monument damaged. Recovered the monument, top bent over, at record bearing and distance from the Red Pine NBT. The B.Cherry NBT is gone. Removed the disturbed monument and drove a new monument in its place. The monument is 20' south of the centerline of Co. Rd 455, in the grassy shoulder.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"IDx36" I.pipe with plastic cap
 #33986 6" below ground. Blazed,
 scribed, and set measuring nails in:
 20" Red Pine N49W 103.3' "1/4" *
 5" Red Pine N34W 79.35' "1/4S NBT"
 5" Maple N11E 52.8' do
 8" Red Pine S17E 46.6' do
 Bearings are magnetic. Distances are to
 nail with tag. * denotes 1960 NBT.



Signed by Stephan J. Szyszkoski Date 12/5/02
 Surveyor's Michigan License No. 33986