

LAND CORNER RECORDATION CERTIFICATE
Finding Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce

(County)

Located In:

Corner Code #

1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S 34	T 47N R 10W	16
	S 34	T 47N R 10W	13
3. Miscellaneous Property in Sec.	S	T R	_____
	S	T R	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 19 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (16-Sec. 34) East 1/16 corner between Sections 34 T47N-R10W and 3 T46N-R10W. Recorded in 1981 by Billy D. Buckler, RLS. 36" T-iron in north edge of blacktop road. 16" W. Birch N8E 60.8', 10" W. Birch N20W 62.8'.
 (13-Sec. 34) Southeast 1/16 corner, Section 34. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (16-Sec. 34) The 1981 monument was not recovered. The 1981 W. Birch NE was recovered at record bearing and distance from the position subsequently monumented. The W. Birch NW was not recovered. Reestablished the corner at the 1981 position, being midway and on line between Section and Quarter corners 1322.11' east and west. The center of County Rd. 407 is 7.6' south. A trail runs north from the corner.
 (13-Sec. 34) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The center of a N-S trail is 32.5' east of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (16) Set 1"IDx36" I.pipe with plastic cap stamped "MICH DNR LS33986" driven flush to blacktop surface of county rd. Blazed, scribed, and set measuring nails in:
 12" twin Maple N38W 71.1' "E1/16 BT"
 8" Balsam S11W 59.4' do
 5" Cedar S14W 92.95' do
 18" W. Birch N10E 61.4' "E1/16"
 Bearings are magnetic. Distances are to nail with tag.
 Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986
 (13) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:
 10" Maple S46W 4.15' "SE1/16 BT"
 6" Maple S43W 17.3' do
 10" Maple East 17.65' do
 6" W. Birch N16E 51.55' do
 Set a cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
 Date 8/6/02

