

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce
 (County)

Located In:	Corner Code #
1. Public Land Survey	T ___ R ___
	T ___ R ___
	T ___ R ___
	T ___ R ___
2. Property Controlling in Section	S <u>34</u> T <u>47N</u> R <u>10W</u> <u>14</u>
	S ___ T ___ R ___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___
	S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 19 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (14-Sec. 34) South 1/16 between Sections 34-35. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (14-Sec. 34) Established the corner midway and on a line of mean true bearing between Quarter corner 1334.50' north and Section corner 1334.50' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Set 1"IDx36" I.pipe with 4" alum.
 MDNR cap. Blazed, scribed, and set
 measuring nails in:
 8" twin Maple N27W 13.5' "S1/16 BT"
 6" Maple in clump S04W 18.5' do
 8" Balsam S48W 36.75' do
 6" twin Maple N76E 19.45' do
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/6/02