

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T47N R 10W	B9
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File
Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9	●												
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on June 18, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (B9) Quarter corner common to Sections 19 and 30. 1853 - Remonumented by Geo.H.Cannon, Deputy Surveyor, on the Section line between Section corner N89deg. 44'E 40.08 chains and Section corner on the Range line N89deg. 03'W 39.20 chains. Set post (same point as old 1/4 cor. Old BTs Hem 7 N40E 26 links, Beech 9 S70W 36 links). New BTs Hemlock 10 N35E 26 links, Beech 7 S69W 35 links. 1975 - Billy D. Buckler RLS: Replaced corner at an old wood post, believed set by H.Lawrence, RLS. Found no original evidence. Set 1" pipe with 4" MI Dept. of Natural Resources cap. 28" W.Pine N53W 34.5', 12" Spruce S55E 12.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (B9) The original post and accessories were not recovered. Found the 1975 monument of record in good condition and at record bearing and distance from the 1975 28" W.Pine witness tree N53W, in good condition. The Spruce NBT was not recovered. It appears from the record that the corner has stood in this position for many years and I accept same as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (B9) Found 1"ID I.pipe with 4" MI DNR cap. Set measuring nail with yellow plastic MDNR tag in the side of the following:
 4" W.Pine S78W 6.05' mrkd "1/4S NBT"
 4" Balsam S26W 6.7' do
 6" Balsam S05E 15.85' do
 36" W.Pine N48W 35.8' mrkd "1/4S" (1975 NBT)
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski Date 12/20/07

Surveyor's Michigan License No. 33986