

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T47N R 10W	C9
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on June 18, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (C9) Corner common to Sections 19-20-29-30. 1853 - Remonumented by Geo.H.Cannon Deputy Surveyor: Set post (same point as old 1/4 cor. Old BTs Beech 9 S08E 38 links, Beech 7 N78W 24 links. New BTs Beech 7 N79W 24 links, Beech 10 S05E 40 links. 1975 - Reestablished by Billy D. Buckler RLS: "Placed corner by proportionate measure from corner to East and West and in line with old fences. Corner lies in East edge of old road bed". Placed 3/4"x32" pipe. 8" Maple N61E 77.8', 10" Maple clump S62W 47.2'. 1984 - Rewitnessed by G.W.Wiggins RLS: "Buckler placed this corner by proportionate measure...Re-witt. this corner as the bearings were recorded wrong". 1" pipe with plastic RLS cap. 10" Maple clump N61W 47.2', 8" Maple S67W 77.8', 8" Maple N84E 43.0', 10" Beech N82W 73.2'. 1995 - remonumented in the 1984 position by Keith Waters PS 33142, who set a 1/2" rebar and placed nails with tags in the 1984 witness trees. (drawing of survey project #95200). NBTs 15" Beech N88W 73.10', 11" S.Maple S58W 77.47', 4" S.Maple East 34.43', 9" S.Maple N61E 47.70'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (C9) Found a 1/2" rebar, disturbed, bent over, but in the proper place and in accord with the 1984 and 1995 witness trees, with exception of the 1984 10" Maple clump, the bearing of which was found to be N61E, not N61W as stated in the 1984 record. I accepted the position of the monument as the best available evidence of the position of the original corner. Removed the 1/2" bent rebar and installed, in its place, and in accord with the record witnesses, a new monument as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (C9) Set 5/8"x18" rebar capped and yellow plastic cap stamped "MICH DNR LS33986". Fd. nail with tag stamped "PS 33142" in the following:
 11" Maple S67W 77.8'
 Maple N84E 43.0'
 15" Beech N82W 73.2'
 Set nail with MDNR tag in the side of:
 10" Maple clump N61E 47.2'
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski Date 12/20/07

Surveyor's Michigan License No. 33986