

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>10W</u>	<u>C10</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

I, Stephan J. Szyszkoski, in a field survey on June 20, 2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (C10) Quarter corner common to Sections 29 and 30. 1853 - Remonumented by Geo. Cannon, Deputy Surveyor, at a position S00deg. 17'W 40.13 ch. from C9 and N00deg. 15'E 40.07 ch. from C11. Set post (same point as old 1/4 cor. Old BTs Fir 9 S39E 6 links, Beech 10 S67W 26 links) New BTs: Beech 12 S65W 24 links, Balsam 8 S38E 6.5 links. 1957 - Reestablished by Billy D. Buckler RLS from orig. Tamarack line tree 8.65 ch. south and on a line produced through the tree and the Sec. Cor. 29-30-31-32. Set 1"ID I.pipe with 4" brass cap. 12" J.Pine S67E 100.5 links, 16" W.Pine S56W 112 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (C10) The original post and accessories were not recovered. Found the 1957 monument in good condition and at record bearing and distance from the remaining 1957 NBT W.Pine S56W (now 30" DBH) in good condition. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (C10) Fd. 1"ID I.pipe with 4" brass MI Dept. of Conservation tablet. Set measuring nail with MDNR tag in the side of the following:
 30" W.Pine S62W 74.35' mrkd "1/4S" (1957 NBT)
 8" Balsam N07E 15.98' mrkd "1/4S NBT"
 8" Balsam S12E 9.18' do
 7" Balsam West 28.07' do
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski Date 12/20/07

Surveyor's Michigan License No. 33986