

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>47N</u> R <u>10W</u>	<u>L7</u>	
	T <u>47N</u> R <u>10W</u>	<u>M7</u>	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims			

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Feb 28 2007

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- (L7) Quarter corner common to Sections 13 and 24. 1968 - Billy D. Buckler RLS remonumented the corner in the original position from a Pine B.T. N56W 81 links. Set 1" I.pipe with 4" aluminum cap. 13" W.Pine S34W 6.0', 15" Tamarack N75W 37.8'.  
(M7) Section corner common to Sections 13-24 T47N-R10W and Sections 18-19 T47N-R09W. 1963 - Billy D. Buckler RLS reestablished the corner by single proportionate measurement. Set 1" pipe with 4" aluminum cap. No witnesses available.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (L7) Recovered the 1968 monument in good condition and at record bearing and distance from the 1968 witnesses. The Tamarack is now a stump. The W.Pine is in good condition. The original Pine B.T. is no longer standing. A search for its remains was not practical due to snow cover and was not attempted.  
(M7) Recovered the 1963 monument in good condition, apparently undisturbed. This corner is being recorded in order to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| (L7) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>19" W.Pine S27W 7.2' mkrd "1/4S" *<br>14" Tamarack S05E 33.75' "1/4S NBT"<br>9" Cedar S23E 42.7' do<br>7" Spruce S79E 22.8' do<br>Bearings are magnetic. Distances are to nail with MDNR tag. * denotes 1968 NBT. | (M7) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:<br>2" Tamarack N07W 51.15' no markings<br>5" Tamarack N42W 49.55' mkrd "S13 NBT"<br>4" Tamarack S14E 76.9' "S19 NBT"<br>8" Tamarack N55E 56.3' "S18 NBT"<br>Bearings are magnetic. Distances are to nail with MDNR tag. |
|---|--|



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 6/6/07

For the Michigan Department of Natural Resources, Office of Land and Facilities