

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>47N</u> R <u>10W</u>	<u>M5</u>
	T <u>47N</u> R <u>10W</u>	<u>M6</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Mar 01 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (M5) Section corner common to Sections 12-13 T47N-R10W and Sections 7-18 T47N-R09W. 1964 - Reestablished by single proportionate measurement by Frank Bray RLS. Set 1" iron pipe with 4" aluminum cap. 10" J.Pine S22W 87 links, 26" W.Pine S31E 86 links.
 (M6) Quarter corner common to Section 13 T47N-R10W and Section 18 T47N-R09W. 1963 - Reestablished by Billy D. Buckler RLS at an old wood stake found in accord with original W.Pine line tree. Set 1" pipe with 4" alum. cap. 16" Red Pine N09E 32 links, 10" J.Pine N80W 30 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (M5) Recovered the 1964 monument in good condition and at record bearing and distance from the 1964 witnesses. The J.Pine is now a stump. The W.Pine is in good condition. This corner is being recorded in order to update the accessories.
 (M6) Found the 1963 monument in good condition and at record bearing and distance from the 1963 witnesses. The J.Pine is standing dead. The R.Pine is in good condition. This corner is being recorded in order to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (M5) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
30" W.Pine S33E 57.3' old blazes *
22" W.Pine S01W 60.9' mrkd "S13 NBT"
8" R.Pine S24W 52.3' do
16" W.Pine S53W 79.1' do
Bearings are magnetic. Distances are to nail with MDNR tag. * denotes 1964 NBT. | (M6) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
19" R.Pine N13E 21.95' mrkd "1/4S" *
6" R.Pine S84W 19.4' "1/4S NBT"
6" Spruce S21W 22.2' do
6" W.Pine S08E 29.55' do
Bearings are magnetic. Distances are to nail with MDNR tag. * denotes 1963 NBT. |
|---|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/6/07

For the Michigan Department of Natural Resources, Office of Land and Facilities