

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 10W T 47N R 10W T _____ R _____	C8 D7 _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____ S _____ T _____ R _____	_____ _____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on C8 09/18/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C8) Quarter corner common to Sections 19 and 20. 1973 - Billy D. Buckler RLS placed a 1"ID iron pipe with 4" MI Dept. of Natural Resources cap at the position of a found 4" pipe which had been set by an unknown surveyor. New bearings: 16" Y.Birch S03E 53.2', 8" Maple N43W 32.9'. Corner lies 150' East of Old Co. Rd. 407.

(D7) Quarter corner common to Sections 17 and 20. 1973 - Billy D. Buckler RLS reestablished the corner position midway and on line between two Section Corners. Set 1"IDx36" pipe with 4" brass MI Dept. of Natural Resources cap. 9" Hard Maple S19E 9.0', 9" Hard Maple N79E 14.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C8) Found the 1973 monument in good condition and at record bearing and distance from the 1973 witness Y.Birch, now standing dead. The 1973 Maple was not recovered. This monument is being recorded in order to update the accessories.

(D7) Recovered the 1973 monument in good condition and at record bearing and distance from the 1973 witnesses, both in good condition. This corner is being recorded in order to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C8) Fd. 1"ID I.pipe with 4" MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 6" Balsam N42E 6.65' mrkd "1/4S NBT"
 11" Maple S64E 28.48' do
 5" twin Y.Birch N24W 12.62' do
 7" Balsam West 25.76' do
 Bearings are magnetic.

(D7) Fd. 1"ID I.pipe with 4" brass MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 12" Sugar S22E 8.86' 1973 witness
 13" Sugar N83E 15.42' do
 12" Maple N05W 8.87' mrkd "1/4S NBT"
 11" Maple N64W 10.6' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/20/2008



For the Michigan Department of Natural Resources, Office of Land and Facilities