

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 47N R 10W	D9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9		●											
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 09/18/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(D9) Quarter corner common to Sections 20-29. 1975 - Billy D. Buckler RLS reestablished the corner position midway and on line between Section corners. Set 1"IDx36" I.pipe with 4" MDNR cap at the corner. 6" Maple S53E 52.5', 8" Maple N16E 17.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D9) Found the 1975 monument in good condition and at record bearing and distance from the 1975 witnesses, both in good condition. This corner is being recorded in order to update the accessories.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D9) Fd. 1"ID I.pipe with 4" MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 9" Maple S48E 52.75' mrkd "1/4S" 1975 witness  
 13" Maple N21E 17.9' do do  
 9" Maple N54W 23.23' mrkd "1/4S NBT"  
 9" twin Maple N71E 28.9' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/20/2008  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities