

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 47 N. X , R. 11 X W.	H-3, J-3, L-3
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-1, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corners placed by Geo. H. Cannon D.S. in 1854.

- H-3 Quarter Corner bet. Sec's. 3-10.
Bearings were: Sugar 10", N85°E, 29 lks & Sugar 15", S66°W, 25 lks.
- J-3 Quarter Corner bet. Sec's. 2-11.
Bearings were: Beech 8", N28°E, 20 lks & Beech 8", S40°W, 22 lks.
- L-3 Quarter Corner bet. Sec's. 1-12.
Bearings were: Sugar 13", N51°E, 18 lks & Beech 10", S67°W, 24 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-3 Corner re-established midway and on line bet two Section Corners.
- J-3 Corner re-established midway and on line bet two Section Corners.
- L-3 Corner re-established midway and on line bet two Section Corners.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at both corners.

- H-3 New Bearings: 16" Maple, N82°W, 69.6' and 8" Maple, S23°W, 48.1'.
- J-3 New Bearings: 10" Maple, N70°W, 61.1' and no others available.
- L-3 New Bearings: 16" W. Pine, N36½°E, 79.8', and no others near.

SIGNED BY Billy D. Buckler
 Billy D. Buckler
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

DATE 2-15-77



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____