

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Two Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY.....	T. <u>47</u> N. <u>9</u> R. <u>11</u> E. <u>W.</u>	G-6 G-5
2. PROPERTY CONTROLLING IN SECTION.....	T. _____ N. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION.....	T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey of G-6, 4/28-G-5, 5/8 1970, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-6 $\frac{1}{4}$ Cor. bet. Secs. 15-16, set originally by Geo H. Cannon, D.S. in 1853, while making a Correctional Survey of the Twp.

Bearings:

Sugar 15" S10°E 5 Lks

Sugar 8" N32°W 19 Lks

G-5 Sec. Cor. 9-10-15-16, set by Geo H. Cannon, D.S. who defaced the old corner and set a correct one.

Bearings:

Beech 11" S61°W 12 Lks and Sugar 9" N74°E 32 Lks

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-6 Corner replaced at a wood post, set by unknown surveyor. Distance, South to a good corner is 2620.0'. Corner lies 102' North of an old road intersection.

G-5 Corner replaced, by measuring record distance from an older, unacceptable corner which had been effaced by the Deputy Surveyor, Cannon. Found remains of possible Sugar bearing. Found the effaced Hemlock, 61 Lks South and 22 Lks West of corrected corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6 Placed 1" pipe with 4" aluminium cap at corner.

New Bearings:

10" Hard Maple S55°W 22.0'

9" Soft Maple S38°E 15.7'

G-5 Placed 1" pipe with 4" Aluminium cap at corner.

New Bearings:

8" Soft Maple N60°W 8.9'

11" Hard Maple N74°E 5.4'

SIGNED BY Billy D. Buckler

DATE 7/19/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____