

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Two Corners.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. <u>11</u> E. <u>W.</u>	G-10 H-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on G-10, 5/24-11, 6/20-71, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-10 $\frac{1}{4}$ Cor. bet. Secs. 27-28, set by Geo H. Cannon, D.S. in 1853, while making a Correctional Survey of the TWP.

Bearings:

W. Pine 24" S75°E 75 LKS

W. Pine 10" N36°W 19 LKS

H-11 $\frac{1}{4}$ Cor. bet. 27-34, set by Geo H. Cannon, D.S.

Bearings:

W. Pine 20" N5°W 26 LKS

Balsam 12" S60°E 12 LKS

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-10 Corner replaced from two probable witnesses, which are now only stump bottoms. Position checks well with an original corner, $\frac{1}{2}$ mile to North. Corner lies 200' North of a road.

H-11 Corner replaced from probable pine witness. Found some scars on Pine stump. Distance checks well to good corner, $\frac{1}{2}$ mile, East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10 Placed 1" pipe with 4" aluminium cap at corner.

New Bearings:

9" B. Cherry West 23.5'

17" W. Pine N5°E 110.3'

H-11 Placed 1" pipe with 4" aluminium cap at corner.

New Bearings:

9" W. Pine S70°W 9.5'

12" W. Pine N85°E 43.6'

SIGNED BY Billy D. Buckler
Billy D. Buckler

DATE 7/19/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____