

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
Luce Co. Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 47 N. 30 R. 11 E. W.	G-11 F-11
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 6/20 1971, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- G-11 Sec. Cor. 27-28-33-34, set originally by Geo H. Cannon, D.S. in 1853, while making a Correctional Survey of the Twp.  
Bearings:  
    - Y. Birch 8" N74°W 32 LKS
    - Hemlock 9" S40°E 34 LKS
  - F-11 1/4 Cor. bet. Secs. 28-33, also set by Geo H. Cannon, D.S.  
Bearings:  
    - W. Pine 8" N66°W 28 LKS
    - Maple 9" S45°E 32 LKS
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- G-11 Found nothing at this corner, so re-established by proportionate measure from; 1/4 Cor. 1/2 mile, North. Corner lies in SW border of an old, burnt opening as indicated by record notes.
  - F-11 Found a 1/2" x 36" iron rod, buried in East edge of Co. Road # 415. Wood Post at corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- G-11 Placed 1" pipe with 4" aluminium cap at corner.  
New Bearings:  
    - 36" W. Pine Stump S47°W 127.9'
  - F-11 re-witnessed Iron Rod.  
New Bearings:  
    - 8" Soft Maple N57°W 70.0'
    - 10" Aspen S65°E 22.6'

SIGNED BY Billy D. Buckler DATE 7/19/72  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)  
 FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_  
 APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)