

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Lucas Co.

Two Corners

THE CORNER OF --	LOCATED IN --	D. CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>57</u> N. R. <u>11</u> E.		D-7 Meander cor., 2.51 chs West of sec. D-7
2. PROPERTY CONTROL- ING IN SECTION _____ T. _____ S. R. _____ E.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ S. R. _____ E.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLASS _____		

NUMBER OF CORNER CORNER AND
PLAT CORNER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index map diagram - over) were, in a field survey on 7/19/72, established, re-established, monumented, re-monumented, uncovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 7/19/72, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

D-7 $\frac{1}{4}$ Cor. bet. Secs. 19-20, set by Geo H. Cannon, D.S. in 1853, (originally) while making a Correctional Survey of the Twp.
Bearings were:

Neolock 10° 30' 30" S 24.425
J. Birch 16° 16' 30" W 32 LIS

M.C. Meander corner bet. 19-20, also set by Geo H. Cannon, D.S.
Bearings were:

W. Pine 15° 32' 15" E 7 LIS
W. Pine 10° 31' 15" E 22 LIS

B. Description of corner evidence found and/or method applied in locating or re-establishing corner:

D-7 $\frac{1}{4}$ Cor. re-established at record distance (2.51 chs.) and bearing (S89° 36' E) from the Meander Corner, on East shore of Bass Lake.

M.C. Replaced from two Pine stump bottoms in proper position. Checked bearing to an original M.C. bet. Secs 19-20, to agree with record. Corner lies 18' East of present water edge.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminum cap at both corners.

D-7 New Bearings:

1 1/2" Soft Maple N13° E 38.4'
7" Soft Maple N51° W 13.5'

M.C. New Bearings:

8" W. Pine N00° W 52.0'
9" Soft Maple S45° E 88.7'

SIGNED BY Billy D. Buckler

DATE 7/19/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____