

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Two Corners.

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>47</u> N. S., R. <u>11</u> E. W.	C-5 C-6
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 7/10 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C-5 Sec. Cor. 7-8-17-18, originally placed by Geo H. Cannon, D.S. in 1853, while making a Correctional Survey of this Township.

Bearings were:

W. Pine 16" N34°E 14 Lks

Y. Birch 10" S57°W 28 Lks

C-6 ¼ Cor. bet. Secs. 17-18 also set by Geo H. Cannon, D.S.

Bearings were:

Sugar 18" N27°E 27 Lks

Beech 8" S58°W 8 LKS

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-5 Found two wood posts, set by C.C.I. Cruisers. Found blazes to N-S-E-W. Logging operations apparently removed any evidence of original witnesses.

C-6 Corner placed 5.0' North of a squared tree. Found line of blazes to N-S-E. No evidence remains of original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at both corners.

C-5 New Bearings:

15" Soft Maple S22°W 51.7'

6" Soft Maple N77°E 20.4'

C-6 New Bearings:

18" Hard Maple S89°W 10.2'

13" Beech N20°W 22.0'

Billy D. Buckler

SIGNED BY Billy D. Buckler DATE 7/19/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8827 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____