

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. Two Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 47 N. R. 11 W.	H-6,
2. PROPERTY CONTROLLING IN SECTION 15 _____	T. 47 N. R. 11 W.	8, Sec. 15
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Duckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 5/26 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 H-6 Center of Section 15

8, Sec. 15 West 1/16 Cor. of Sec. 15.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H-6 Center of Section placed at intersection of lines connecting opposite $\frac{1}{4}$ Corners.
 8, Sec. 15 West 1/16 Corner placed midway bet. Center Corner and the West $\frac{1}{4}$ Cor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed 1" x 36" pipe with Dept. Cap at both corners.

H-6 New Bearings: 10" W. Pine N10 $\frac{1}{2}$ °E 61.4' and 14" B. Cherry N81°E 26.8'
 Corner lies 58' North of County Rd. 422.
 8, Sec. 15 New Bearings: 8" Maple N74°W 29.0' and 8" Maple S41 $\frac{1}{2}$ °W 41.2'
 Corner lies 81.4' North of County Rd. 422.

SIGNED BY Billy D. Duckler DATE 6/27/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)