

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co. Two Corners.

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|--|---------------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>47</u> N. S. R. <u>11</u> E. W. | H-5, I-6 |
| 2. PROPERTY CONTROLLING IN SECTION _____ | T. _____ N. S. R. _____ E. W. | _____ |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S. R. _____ E. W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 5-16 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- H-5 1/4 Cor. bet. Secs. 10-15, set by Geo. H. Cannon D.S. in 1853, while making a correctional survey of this twp.
Bearings were: Beech 14" S10°W 19 lks. and Y. Birch 10" N50°E 19 lks.
 - I-6 1/4 Cor. bet. secs. 14-15, set by Geo. H. Cannon D.S. in 1853.
Bearings were: Maple 12" S69°W 27 lks. and Y. Birch 14" S78°E 30 lks.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- H-5 Corner re-established midway and on line bet. Sec. Cors.
 - I-6 Corner replaced from remains of a Y. Birch bearing tree, a stump with scars and part of lower blaze in evidence.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- Placed 1" x 36" pipe with Dept. Cap at both corners.
 - H-5 New Bearings: 14" Maple S87°E 43.9'
10" Maple S37°W 40.8'
Corner lies 39.5' North of Murray lake road.
 - I-6 New Bearings: 15" W. Spruce S52°W 46.9'
5" S. Maple S88°W 9.6'
Corner is 15' South of road.

SIGNED BY Billy D. Buckler DATE 6/27/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)