

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Three Corners.

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>47</u> N. <u>X</u> R. <u>11</u> E. <u>W.</u>	K-2, K-3, K-6
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 5-25 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- K-2 ¼ Cor. bet. Sec. 1-2, set originally by Geo. H. Cannon D.S. in 1853, while making a correctional survey of this top.  
Bearings were: Cedar 8" S39°E 13 lks. and Hemlock 16" N74°E 26 lks.
- K-3 Sec. Cor. 1-2-11-12, set by Geo. H. Cannon D.S. in 1853.  
Bearings were: Beech 12" S63°E 25 lks. and Maple 9" N52°W 5 lks.
- K-6 ¼ Cor. bet. Sec. 13-14, set by Geo. H. Cannon D.S. in 1853.  
Bearings were: Sugar 15" S60°E 20½ lks. and Sugar 10" S43°W 26 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- K-2 Corner placed at wood post, set by unknown Surveyor.
- K-3 Corner placed as set by unknown Surveyor. Found trees marked as witnesses, more than 40 Years old.
- K-6 Corner replaced at an old blazed maple tree. Found no evidence of original witnesses. Position checks with other corners in area.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- K-2 Placed 1" x 36" pipe with Brass Dept. cap.  
New Bearings: 4" Cedar S43°E 45.6' and 4" Cedar S11°W 38.5'  
Corner lies on N. & S. brushed line.
- K-3 Placed 1" x 36" pipe with copper Dept. cap.  
New Bearings: Twin Maple N30°E 15.2' and 10" Maple N46°W 9.0'  
Corner lies 33' West of N. & S. brushed line.
- K-6 Placed 1" x 36" pipe with Brass cap at corner.  
New Bearings: 8" Maple N16°E 17.9' and 9" Maple N52°W 35.5'  
Corner lies on east side of 12" squared Maple on N. & S. brushed line.

SIGNED BY Billy D. Buckler DATE 6/27/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 3887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_